



(D)	
FR2	= 2" TOTAL MOVEMENT
FR3	= 3" TOTAL MOVEMENT
FR4	= 4" TOTAL MOVEMENT

## HW-D-0421 CONCRETE SLAB

### NOTES:

- 1.) SINGLE LAYER OF 5/8" TYPE X DRYWALL FOR 1 HOUR AND 2 LAYERS FOR 2 HOURS.
- 2.) ALWAYS CHECK UL FIRE RESISTANCE DIRECTORY FOR COMPLETE DESIGN REQUIREMENTS.